

Nong-tako Interchange



Client: Department of Highways (DOH)

Date: 2007-2008

Services Rendered:

- » Feasibility Study
- » Preliminary Design
- » Detailed Design
- » Cost Estimates
- » Tender Documents

Nong-tako Interchange project includes feasibility study and detailed design of the interchange to support Nakhon Sawan ring road network. The structures are cast-in-situ prestressed box-girder with span length 35-40 m. Large diameter bored piles are used to reduce construction time for foundations.